

Contractor Company

Name: _____

REQUEST FOR QUOTE

West Lafayette
Village Furnishing
Concrete Pad
Project

May 28, 2010

Scope /quote form

Scope "A": Concrete Pads for Waste Receptacles in Brick Paver Areas (2 pads)

- 1) Remove enough brick pavers to create a 3' x 3' concrete pad.
- 2) Excavate out sufficient material to pour a new 3' x 3' x 6" thick concrete pad with one layer of 6x6 10/10 wire mesh. Concrete to be 4000psi limestone mix.
- 3) Cut and re-install brick pavers against the new concrete pad.
- 4) These locations are in the brick paver area along the north side of South Street between Chauncey and Northwestern Ave.

Scope "B": Concrete Pads for Waste Receptacles in Mulch Area (1 pad)

- 1) Remove enough mulch and soil to create a 3' x 3' concrete pad. Save mulch to fill around completed pad.
- 2) Excavate out sufficient material to pour a new 3' x 3' x 6" thick concrete pad with one layer of 6x6 10/10 wire mesh. Concrete to be 4000psi limestone mix.
- 3) Fill around the new pad and re-mulch.
- 4) This location is in a mulch bed on the west side of Chauncey Street between South Street and Columbia Street just south of the alley.

Scope “C”: Concrete Pad for Bench in Brick Paver Area (1 pad)

- 1) Remove enough brick pavers to create a 3’ x 8’ concrete pad. Remove brick so that only full brick are remaining around the pad.
- 2) Excavate out sufficient material to pour a new 3’ x 8’ x 6”thick concrete pad with one layer of 6x6 10/10 wire mesh. Concrete to be 4000psi limestone mix.
- 3) Re-install brick pavers against the new concrete pad.
- 4) This location is next to the West Lafayette Public Library on the north side of Columbia Street. There are several benches already in place utilizing the same details.

Scope “D”: Concrete Pad for Kiosk in Brick Paver Area (1 pad)

- 1) Remove enough brick pavers to create a 3’ x 3’ concrete pad.
- 2) Excavate out sufficient material to pour a new 3’ x 3’ x 12”thick concrete pad with one layer of 6x6 10/10 wire mesh. Concrete to be 4000psi limestone mix. NOTE THIS PAD IS 12” THICK
- 3) Cut and re-install brick pavers against the new concrete pad.
- 4) This location is along South Street in front of Greyhouse coffee.

General notes:

- 1) Contractor is responsible for all utility locates including City of State signal infrastructure.
- 2) All areas will be hand excavated
- 3) Remove all waste material from site
- 4) All remaining brick pavers will be saved and turned over to the City.
- 5) Contact Tom Gall, 426-1743 to arrange to look at the locations in person.

Scope A: Concrete Pads for Waste Receptacles in Brick Paver Areas (2 pads)

Lump Sum _____

Scope B: Concrete Pads for Waste Receptacles in Mulch Area (1 pad)

Lump Sum _____

Scope C: Concrete Pad for Bench in Brick Paver Area (1 pad)

Lump Sum _____

Scope D: Concrete Pad for Kiosk in Brick Paver Area (1 pad)

Lump Sum _____

Overall total for scope of project specified _____

SUBMITTED BY

Contractor’s Name: _____

Authorized Signature: _____ **Date:** _____

Addenda(s) _____

June 2, 2010

Re: WL Village Furnishing Concrete Pad Quote
Addendum #1

ADDENDUM #1

- 1.) Scope "A" (waste receptacle pads in paver areas)
Do not excavate below the granular material below the brick pavers. The minimum concrete thickness is to be 4". 6" is preferred if the existing granular material is thick enough to allow that. Watch for the land owners down spout drain in these areas.
- 2.) Scope "B" (waste receptacle pad in mulch bed)
Change the size to be a 6' right triangle to fill the entire area from the walk to the curb. In this area excavate to the full 6" thickens.
- 3.) Scope "C" (bench pad)
Same excavation detail as noted in item 1 above.
- 4.) Add Scope "E" Replace missing pavers
Replace missing concrete pavers on south side of South Street at the intersection of South and Chauncey Streets, SW corner. Approximately 10 sf. Pavers will be provided by City of West Lafayette and picked up at the Street Department.

NOTE: HAND WRITE IN THIS SCOPE ON THE QUOTE FORM PROVIDED IN THE ORIGINAL QUOTE DOCUMENT.

- 5.) Add Schumann Custom Building and Landscaping to the quote list.

Acknowledge the receipt of this addendum in writing on the quote.

End Addendum #1