



NOTES:

1. ALL DRIVES HAVE 10'-0" RADII ON BOTH SIDES UNLESS OTHERWISE NOTED.
2. NO WORK IS TO EXTEND BEYOND THE CITY RIGHT-OF-WAY AS INDICATED.
3. ALL UNIVERSAL ACCESS RAMPS HAVE A 6'-0" OPENING AT THE CURB UNLESS OTHERWISE DIRECTED BY ENGINEER.
4. ALL 2'x2' TRUNCATED DOME PLATES ON THE RAMPS ARE EAST JORDAN 7005 (OR APPROVED EQUIVALENT).
5. UNLESS RIGHT-OF-WAY ALLOWS, ALL RAMPS SHALL HAVE CURB ON THE BACK. ENGINEER WILL INSTRUCT.

LEGEND

REMOVE, DO NOT REPLACE

ightharpoonup

2

MATCH EXISTING

EAST JORDAN 2'x2' T ATED DOME PLATES, TRUNC-s, 7005

 (ω)

1:12 SLOPE MAX.

4

TREE SCHEDULE

A - SWEET GUM - PROTECT

B - SWEET GUM - PROTECT

C - NORWAY MAPLE - REMOVE

D - NORWAY MAPLE - REMOVE

E - SILVER MAPLE - REMOVE

G - TULIP - PROTECT

H - TULIP - PROTECT

J - TULIP - PROTECT

K - PEACH - REMOVE

L - PEACH - REMOVE SYCAMORE - PROTECTSIBERIAN ELM - REMOVESIBERIAN ELM - REMOVE

DATE:

1 0-001

SHEET NUMBER

×

C100

DATE: CHECKED BY: DRAWN BY: 04-26-2010 DMB ELC

2010 CDBG SIDEWALK PROJECT **ROBINSON STREET**

CONSTRUCTION PLANS

DEHART TO STADIUM





