

Contractor Company

Name: _____

REQUEST FOR QUOTE

West Lafayette
2011 Northwestern Ave Sidewalk
Brick Paver Replacement
Project

April 7, 2011

ADDENDUM 1
April 19, 2011

Scope /quote form

Scope "A": Normal Duty Concrete Brick Pavers along the east side of Northwestern

- 1) Remove existing brick paver band at the curb line and dispose of offsite. This project begins at the south edge of the Panda Express site (shown as Razor's edge on plan) where new pavers have already been installed and extends south to until it meets the concrete in front of the coffee shop at on Northwestern. The contractor is responsible for measuring the actual area to be removed and replaced. The plan included in this package is for general information only. It is not to scale and is from the original project.
- 2) Provide and install 1" of leveling sand directly under the pavers.
- 3) Provide install in a similar pattern to match the existing pavers new normal duty concrete pavers. Pavers are to be compacted into place installed 1/4" above the adjacent concrete.
- 4) If new pavers do not fit the existing space cut the curb side pavers to fit.
- 5) Pavers are to be Hollandstone by Belgard 60mm. Color: Antique. Provide sample brick for approval prior to installation.

Scope “B”: #53 Crushed Limestone

- 1) Provide and install 10 tons of compacted #53 crushed limestone for sub base if needed. Payment will be per ton installed based on delivery tickets.
- 2) Installation of this material will be by approval of the project manager only.

Alternate Scope “C”: Panda Express Outer Paver

- 3) Provide and install pavers per as described in “Scope A” from the alley south of Panda Express on the curbside band only from this point on Northwestern Ave north and then east around the building to the Panda Express curb cut.
- 4) This contractor will initially remove the brick at the Northwestern/Columbia Street radius to allow the City of West Lafayette’s contractor to build a 5’ wide concrete curb ramp facing due north to match up with the one across Columbia Street.
- 5) The contractor is to INCLUDE a \$700 dollar allowance in this alternate scope for rental of construction barrels and temporary signage to create a temporary ADA walking route for the time the curb ramp is not available for pedestrians to cross Columbia Street. The allowance is for the direct cost of rentals or signage created for such purpose and the contractor must provide documentation of the cost with any claim submitted (this is to be paid at cost without markup). The contractor will provide labor to maintain the set up as needed through the project as part of the quote. This Temporary path will start at the Panda Express curb cut on Columbia and extend back to the existing crosswalk to the north.

Prices are lump sum per item unless noted otherwise. **Owner must be notified and approve of work beyond the quantities given in the Request for Quote form.**

Scope A: East Side Northwestern Pavers

Lump Sum _____

Scope B:#53 Crushed Limestone installed

10 tons Unit Price _____ Total _____

Total for scopes A and B _____

Alternate Scope C: Panda Express outer paver band

This quote includes the \$700 allowance \ADD Lump Sum _____

SUBMITTED BY

Contractor’s Name: _____

Authorized Signature: _____ **Date:** _____

Addenda(s) _____