

CITY OF WEST LAFAYETTE, INDIANA

To: RL Turner Corporation
 1000 West Oak Street
 Zionsville, IN 46077

Work Order No.: 1-R1
 Date: February 15, 2013
 Project Name: North Side Regional Lift
 Station and Force Main
 Improvements

Specification Section: 00500
 Drawing Reference: SD01 – SD05

Note: Revisions to Work Order No. 1 are shown in **BOLD**.

<u>ITEM</u>	<u>COST</u>	<u>DAYS</u>
1. Modifications to the New 8" Force Main and Milestone #1	\$28,728.00*	98*

Contractor shall install the force main in accordance with the supplemental drawings SD01 – SD05. Contractor shall furnish and install the new 8" force main via horizontal directional drilling between Stations A45+48.95 and A49+25.04 in lieu of open cut. All work is to be in accordance with the Contract Documents. This work shall be Substantially Complete by March 15, 2013. **This cost was reviewed and found to be reasonable.**

*The total cost shall be applied to Contract Item #5 (Work Allowance) in accordance with Specification Section 01291 Part 1.5 of the Contract Documents. The total cost for this work will be established in a separate Work Order. The additional time shall be incorporated within a future Contract Change Order.

2. Addition of Milestone #1A	\$0.00	142**
------------------------------	--------	-------

Contractor shall install the force main along Yeager Road from Station A20+00 to A36+00 in accordance with the supplemental drawings SD02 – SD04. All work is to be in accordance with the Contract Documents. This work shall be Substantially Complete by March 29, 2013.

** The additional time shall be incorporated within a future Contract Change Order. Milestone #1A shall be incorporated into the project constraints at no additional cost.

REASON FOR THIS WORK ORDER: The installation of the new force main was changed from an open cut installation to horizontal directional drill to avoid impacting the Fire Station No. 3 site on Kalberer Road. The alignment along Yeager Road and across Fire Station No. 3 was modified to avoid impacting new construction. Milestone #1A was added to the project constraints to further coordinate with the City of West Lafayette's Yeager Road – Phase II project.

AUTHORIZATION: This Work Order authorizes the work to be completed as outlined above. Contractor is hereby notified to proceed with the work described above immediately.

Work Order No.: 1
Date: February 15, 2013
Project Name: North Side Regional Lift
Station and Force Main
Improvements

PROJECT COMPLETION DATES: Add Ninety-Eight (98) Calendar Days to Milestone #1 only. Add new Milestone #1A: One-Hundred and Forty-Two (142) Calendar Days from Notice to Proceed. Milestone #2 (Substantial Completion) and Final Completion dates shall remain unchanged.

Recommended By:  02/15/13
Project Manager (Greeley and Hansen) Date

Approved By: _____
Utility Director (Wastewater Treatment Utility) Date

Approved By:  2/20/13
Project Manager (RL Turner Corporation) Date
Pres / CEO

January 8, 2013

TO: Jeremy Hardy

RE: Northside Regional Lift Station – COR #1

We are pleased to provide this proposal to provide all labor, material, and equipment necessary to complete the following scope of work.

SCOPE OF WORK

- Directional Drill FM in front fire station in lieu of open-cut trenching
- Certa-Lock Pipe and Fittings

Cost Breakdown

Material.....	\$6,333
Directional Drill Sub...	\$10,374
Labor.....	\$5,753
Equipment.....	\$4,900
<u>OH/P.....</u>	<u>\$1,368</u>
Total.....	\$28,728

Sincerely,

RLTurner Corporation



Michael A. Donner
Project Manager/Estimator

