TECTON
Construction Management, Inc.

TECTON
Construction Management, Inc.

SK-4

19 20 21 22 23 24 25 26 27 28 29 30 31 32

AGGREGATE FASCIA
TOP/FASCIA ELEV. 129'-10"
REGLET
FLASHING
CANT
ROOF
INSULATION (0' MAX. - 4' MIN.)
ROOF SLAB ELEV. 126'-0"
CONC. DOUBLE TEES
LOOSE PLATE
ACOUSTICAL LAY-IN
SUSPENDED CEILING
CEILING EL. 123'-0"
BEAM
L (PAINTED)
PLACE
DION STRIP
ETE SLAB
W.W. MESH
ESTOS TILE
UPPER LEVEL SLAB 114'-0"
LOOSE PLATE
CONC. DOUBLE TEE
CEILING EL. 110'-0"
BEAM
ACOUSTICAL LAY-IN
SUSPENDED CEILING
L W/VINYL WALL FABRIC
ON STRIP
TE SLAB
W.W. MESH
MAIN LEVEL SLAB EL. 100'-0"
LOOSE PLATE
CONC. DOUBLE TEES
½" FURRING STRIPS @ 16" O.C.
CEILING EL. 97'-0"
STICAL LAY-IN
CONCRETE
FACE BRICK (SOLID)
T DIP GALV. L W/
WATERPROOFING
WATERPROOFING
L W/VINYL WALL FABRIC
SLAB W/6x6 19/0
OVER VAPOR
& GRANULAR FILL
LOWER LEVEL SLAB EL. 88'-0"
STRUCTURAL PLANS
FOOTINGS

PRECAST AGGREGATE FASCIA
TOP/FASCIA ELEV. 129'-10"
FLASHING REGLET
S.S. FLASHING
4" FIBER CANT
BUILT-UP ROOF
CONC. INSULATION (VARIES 0' MAX. - 4' MIN.)
ROOF SLAB ELEV. 126'-0"
PRECAST CONC. DOUBLE TEES
STEEL BEAM
CEILING EL. 123'-0"
2'x4' ACOUSTICAL LAY-IN
PRECAST AGGREGATE WALL PANEL
5/8" DRYWALL W/ VINYL WALL FABRIC
4" VINYL BASE
½" EXPANSION STRIP
3" CONCRETE SLAB W/ 6x6-19/0 W.W. MESH
VINYL ASBESTOS TILE
UPPER LEVEL SLAB EL. 114'-0"
PRECAST CONC. DOUBLE TEES
STEEL BEAM
CEILING EL. 110'-0"
2'x4' ACOUSTICAL LAY-IN
PRECAST AGGREGATE WALL PANEL
5/8" DRYWALL (SPRAY GLAZED)
4" VINYL BASE
½" EXPANSION STRIP
3" CONCRETE SLAB W/6x6 19/0 W.W. MESH
VINYL ASBESTOS TILE
MAIN LEVEL SLAB EL. 100'-0"
PRECAST CONC. DOUBLE TEES
PRECAST AGGREGATE WALL PANEL
CEILING EL. 97'-0"
VERTICAL FACE BRICK (SOLID)
FACE BRICK W/ TOP COURSE SOLID
POURED CONCRETE
4" VINYL BASE
½" EXPANSION STRIP
4" CONC. SLAB W/6x6 19/0 W.W. MESH OVER VAPOR BARRIER AND GRANULAR FILL
LOWER LEVEL SLAB EL. 88'-0"
2x4x⅜ HOT DIP GALV. L W/ MASTIC WATERPROOFING
ASPHALT PAVEMENT
SEE STRUCTURAL PLANS FOR ALL FOOTINGS
1"x2'-0" RIGID INSULATION

SECTION 5/5.10
SCALE: ¾" = 1'-0"

PRECAST AGGREGATE FASCIA
TOP/FASCIA EL. 129'-10"
FLASHING REGLET
S.S. FLASHING
4" FIBER CANT
BUILT-UP ROOF
CONC. INSULATION (VARIES 0' MAX. - 4' MIN.)
ROOF SLAB EL. 126'-0"
16 GA. CLOSER PLATE
PRECAST CONC. DOUBLE TEES
STEEL BEAM
CEILING EL. 123'-0"
2'x4' ACOUSTICAL LAY-IN
PRECAST AGGREGATE WALL PANEL
5/8" DRYWALL (PAINTED)
½" EXPANSION STRIP
3" CONCRETE SLAB W/ 6x6-19/0 W.W. MESH
UPPER LEVEL SLAB EL. 114'-0"
16 GA. CLOSER PLATE
PRECAST CONC. DOUBLE TEES
STEEL BEAM
CEILING EL. 110'-0"
2'x4' ACOUSTICAL LAY-IN
PRECAST AGGREGATE WALL PANEL
5/8" DRYWALL (PAINTED)
4" VINYL BASE
½" EXPANSION STRIP
3" CONCRETE SLAB W/6x6 19/0 W.W. MESH
VINYL ASBESTOS TILE
MAIN LEVEL SLAB EL. 100'-0"
16 GA. CLOSER PLATE
PRECAST CONC. DOUBLE TEES
CEILING EL. 97'-0"
2'x4' ACOUSTICAL LAY-IN
POURED CONCRETE
VERTICAL FACE BRICK (SOLID)
FACE BRICK W/ TOP COURSE SOLID
4" VINYL BASE
½" EXPANSION STRIP
VINYL ASBESTOS FLOORING
4" CONC. SLAB W/6x6 19/0 W.W. MESH OVER VAPOR BARRIER & GRANULAR FILL
LOWER LEVEL SLAB EL. 88'-0"
2x4x⅜ HOT DIP GALV. L W/ MASTIC WATERPROOFING
ASPHALT PAVEMENT
SEE STRUCTURAL PLANS FOR ALL FOOTINGS
1"x2'-0" RIGID INSULATION

SECTION 6/5.10
SCALE: ¾" = 1'-0"
USGS ELEV. 740.0' = 100'-0"

NEW WALL
CONCRETE
6" STUD
6" INSULATION
5/8" DRYWALL
6" 5/8"

38' FULL HT
INT WALLS

STANLEY L. DYLONG
INDIANA
1773
STATE
ARCHITECT

WOLVERTON
BEAM
HALLER
SPALTNER
KIRCHOFF

Architects
Engineers

1718 W. 15TH ST.
INDIANAPOLIS
INDIANA
ZIP 46207
AREA CODE 317
635-4473

W INC.

SHEET A-10 OF 20

REVISIONS