

NOTICE TO BIDDERS
CORRECTION
January 28, 2016

The Board of Public Works and Safety of the City of West Lafayette, Indiana will receive sealed bids for **ADA Compliance Work for the City of West Lafayette Parks and Recreation Department** until the hour of 8:30 AM local time on February 23, 2016, at the Office of the Clerk, Room 101, Morton Community Center, 222 North Chauncey Avenue, West Lafayette, IN 47906 for the completion of the work hereinafter listed. The project consists of pouring concrete pads for compliance with the Americans with Disabilities Act in several of the West Lafayette Parks and is being funded by Community Development Block Grant (CDBG) funds, and as such, is subject to meeting the requirements set forth by the United States Department of Housing and Urban Development (HUD) for entitlement grantees. Wage rates on the project shall not be less than the Federal Davis-Bacon wage scale published by the US Department of Labor.

All bids received by said time will be held unopened and then taken to the Board of Public Works meeting in the Multi-Purpose Room at the Morton Community Center, 222 North Chauncey, West Lafayette, IN and there be publicly opened and read aloud. Late bids will be returned unopened. No oral, telephoned, telegraphed, facsimile, or email bids or changes to bids will be considered.

Bids must be entered upon the bid form and the State Form 52414 (R2/ 3-13)/Form 96 (Revised 2013) submitted in triplicate with the bid and non-collusion affidavit properly executed, and must comply with the statutes of Indiana and with the rules and regulation of the State Board of Accounts of Indiana. Bids shall be in a sealed envelope marked **"2016 CDBG ADA Compliance Work for West Lafayette Parks and Recreation"**.

Bids remain in effect for thirty (30) days. The Board reserves the right to reject any or all bids and waive irregularities of bidding. If you have any questions, please call 765-775-5110.

Project Specifications

- 18 Concrete pads 36" (NOT 30") x 48" minimum poured next to existing benches
- 3 Concrete pads 48" x 48" minimum on each usable side of a grill (removal of existing pads) with a minimum of 24" x 24" x 24" concrete base for the grill sleeve.

Four (4) inch minimum concrete pad with three (3) inch minimum compacted #53 aggregate constructed on undisturbed or compacted sub surface. If it butts up against existing concrete, the contractor shall drill and install rebar (#3 or 3/8") and then install expansion joint between the new and old slab. Cross slope of 1.67% (2 % maximum). Contractor will work with Department for location of sleeve for installation of grills. Work to be completed by May 27th, 2016.

Location of Concrete pads:
8 in University Farm Park
5 in Peck-Trachtman Park
4 in Lommel Park
1 in Trailhead Park

Location of Grill pads*:

1 in Tommy Johnston Park

1 in Trailhead Park

1 in University Farm Park

*Work to include removal of existing pads and disposal of old concrete.

CITY OF WEST LAFAYETTE

BOARD OF PUBLIC WORKS & SAFETY

Sana G. Booker, Clerk

Published: January 29 and February 5, 2016