FAIRFIELD CONTRACTORS INC.

3481 CONCORD ROAD P.O. BOX 4427 LAFAYETTE, INDIANA 47903
FAX (765)477-7431 LAFAYETTE OFFICE (765)474-1456

3481 CONCORD ROAD P.O. BOX 4427
LAFAYETTE, INDIANA 47903

Proposal Submitted To: City of West Lafayette	Phone: (765) 775-5130	Date: 7/22/15
Street:	Job Name: Hilton sidewalk	
City, State and Zip Code: West Lafayette, IN 47906	Job Location: Hilton Garden Inn, West Lafayette, IN	
Attention: Ed Garrison	Architect: Date of Plans: Site visit site visit	Job Phone:
Email:		

This Proposal is for material, labor and equipment to perform the below described scope of work. Per drawings referenced above. We reserve the right to review and revise pricing upon receipt of approved drawings if material differences from bid set are noted. Driveway area totals approximately 946 square feet.

Demolition:
Break out and remove existing settled concrete sidewalk in area of trapezoidal shape, approx. 25' long and 17.5' on one end and 14' on the opposite end. Concrete to be removed to back of curb at drive and to joint line in front of portico brick columns. Subbase shall be recompacted in area of suspected settlement and stone subbase shall be added as needed to bring subbase grade up to required elevation . Reasonable attempt will be made to salvage the existing tree grate-frame for re-use by carefully breaking concrete nearby and chipping remaining concrete from frame with Hilti-type hammer drills. If the frame is of cast iron material, it may not be cleanable without breaking. In the event the frame breaks during cleaning, we have not included a replacement frame in this proposal.

Stone subbase:
Install 2-3 inches of crushed #53 limestone subbase in driveway area and compact.

Sidewalk concrete:
Install expansion joint to match existing. Dowel into existing sidewalk with #4 bars, 2 feet on center. Pour back and finish integrally colored concrete with light broom finish. Clear cure to be spray applied. Joint sealant shall be reinstalled following cure time on concrete. Concrete color may not match exactly due to weathering, concrete chemistry and curing conditions.

Lump sum bid amount: $7,498.00

This proposal does not include permits, tap fees, impact or usage fees, geotechnical engineering, field engineering, as builts or third party testing.
This proposal does not include any relocation of underground structures or utilities.
This proposal does not include any payment, performance or 3 year maintenance bonds.
Any unsuitable or deleterious materials to be removed and replaced on a time and material basis if required.
This proposal assumes re-use of existing tree grate and frame. If existing frame breaks during cleaning, a new frame will need to be fabricated or otherwise hastily procured. Cost of new frame not included.

We propose hereby to furnish material and labor – complete in accordance with above specifications for the base bid, for the sum of:

Seven thousand, four hundred ninety eight dollars ($7,498.00)
Payment to be made as follows:

Payment due within 30 days of billing following application of curing compound. All past due accounts bear interest calculated at the rate of 18% per annum, plus costs of collections and are the responsibility of the owner.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to workers are fully covered by Workmen's Compensation Insurance.

Authorized Signature Travis Hunt

Note: This proposal may be withdrawn by us if not accepted within 10 days

Acceptance of Proposal – The above prices, specifications and conditions are satisfactory and are hereby accepted.. Your are authorized to do the work as specified. Payment will be made as outlined above.

Signature _____

Date of Acceptance: _____

Signature _____